Symphony Smart Homes
45 Aspen Glen Ct
Edwards, Colorado 81632
United States

info@symphonysh.com
(970) 519-3013
Matthew Earley
info@symphonysh.com
(970) 519-3013

C4/NoSecurity

Steve Toplets

84 Aspen Meadow Drive
Edwards, Colorado 81632
United States

stopletz1@gmail.com

(469) 879-2511

Presented By

Symphony Smart Homes

Quote Number

Q-196

Presented On

Mar 26, 2026

Version

1

Project Description

PRE-CONSTRUCTION, ENGINEERING, AND COORDINATION

Review plans and RFP requirements for the Topletz Residence. Coordinate with RMGC, electrician, and design team on rough-in pathways, rack location, WAP placement, security panel placement, and all device locations. Confirm backing, conduit, and pathways prior to rough-in. Produce field-ready rough/trim documentation and final integration map.

LOW-VOLTAGE PREWIRE AND BACKBONE

Install and terminate low-voltage cabling for control, audio, network, shade, camera, and security panel systems. Install RG6/U coax at designated locations. Install Cat6 or better to all device locations, home-run to centralized rack. All wiring labeled, tested, and documented.

Shade Prewire
Cat6 and power conductor to all designated shade/window treatment openings. Shade hardware excluded -- prewire only.

Camera Prewire
Cat6 to exterior camera locations -- front entry, rear, garage, driveway. Camera hardware excluded -- prewire only.

Security Panel Prewire
Cat6 to Qolsys IQ Panel 4 at garage entry (primary) and secondary keypad at master bedroom. Panel on dedicated Security VLAN (VLAN 40). Security hardware, sensors, and monitoring provided by Superior Alarm -- not included in this scope.

Conduit
Install conduit from equipment rack to attic for future expansion.

Blocked pathways or rework conditions addressed via change order.

CONTROL4 AUTOMATION AND LIGHTING PLATFORM

Install and configure one Control4 CORE3 controller. Provide fully integrated C4 lighting system (dimmers, switches, keypads) per approved load schedule. C4 native lighting selected per client direction.

Integrate lighting, audio, security panel status, and user interfaces into unified control experience.

Configure Qolsys IQ Panel 4 integration via Cindev DriverCentral driver with SDDP auto-discovery on VLAN 40 for security visibility within Control4.

Install data and power runs to iPad mounting locations at Kitchen/TV Room and Master Bedroom. Provide and configure iPads for system control and dashboard access.

Programming includes room naming, lighting scenes, keypad assignments, audio routing, and core automation. Post-approval changes addressed as billable service.

LIGHTING CONTROL SYSTEM (CONTROL4)

Install and commission C4 lighting devices per approved design. Coordinate with electrician on load wiring and device compatibility. Configure scene logic, keypad functionality, and LED feedback. Validate full operation prior to handoff.

DISTRIBUTED AUDIO SYSTEM

Install centralized rack-based amplification (Triad TS-PAMP8-125-V2 / TS-PAMP4-125-V2 or equivalent) supporting audio zones per approved plan. Install in-ceiling and outdoor speakers. Configure zone control, source access, and grouping through Control4.

NETWORK INFRASTRUCTURE AND SEGMENTATION

Install and configure gateway, switches, and WAPs. Implement VLAN segmentation: Management, Control, AV, Security, and Guest. Qolsys panel on VLAN 40. Validate network performance at commissioning.

RACK, POWER, AND PROTECTION

Build and commission centralized 18U rack. Install managed power distribution with remote reboot. UPS for control and network equipment only (amps excluded). Dedicated 20A circuit by electrician. All high-voltage work by others.

COMMISSIONING, QA, AND HANDOFF

Full system commissioning: device onboarding, firmware verification, control validation, performance testing. Room-by-room verification. Client orientation on system use. Deliver as-built documentation. Sixty (60) day post-commissioning tuning period included.

MONITORING AND SUPPORT

Ongoing monitoring under Symphony Care Addendum. Remote access required.

CLIENT RESPONSIBILITIES

Client/project team provides construction-ready environment with pathways, backing, power, and site readiness. Licensed electrician for all high-voltage. Client maintains internet service and third-party accounts. Timely approvals required. Equipment must be protected from other trades.

PERFORMANCE EXPECTATIONS

System designed for reliable, high-performance smart home experience. Lighting, audio, and UI performance dependent on proper loads, network conditions, and environmental factors. Third-party integrations subject to manufacturer changes.

DESIGN INTENT AND ACCEPTANCE

Proposal reflects intended design per approved plans. Client acknowledges alignment by proceeding. System accepted upon commissioning demonstration and orientation.

EXCLUSIONS

No Sonos, distributed TV audio, video matrix, or HDMI distribution. CORE5 excluded (CORE3 only). 10G switching excluded (1G only). Security hardware (Qolsys panel, sensors, monitoring) by Superior Alarm -- not included. Camera hardware excluded -- prewire only. Shade hardware/motorization excluded -- prewire only. Security sensor prewire not in base scope -- change order pending Superior sensor plan. All work not listed excluded unless added by written change order.

POST-COMPLETION SERVICE

Post-completion service billed per agreement rates. Includes adjustments, reprogramming, additions, and troubleshooting. Service rates defined in project agreement (Section 5). Tuning period adjustments included at no charge for 60 days.

Products

Main Level > Living Room $3,684.74

Distributed Audio $1,099.94

ITEM	QTY	UNIT PRICE	TOTAL
PS **PREWIRE Speaker** 1 16/4 Speaker Wire	1	$125.88	$125.88
Episode ES-ESS-BRKT-IC-6 In-Ceiling Speaker Brackets	1	$28.90	$28.90
Triad Speakers TS-PDX-IC64 Triad PDX Series 4 In-Ceiling Speaker (Each) - 6	2	$472.58	$945.16

Lighting $1,022.97

ITEM	QTY	UNIT PRICE	TOTAL
Control4 C4-KD120-C-SW Contemporary 120V Keypad Dimmer	3	$340.99	$1,022.97

Integrated Control System $593.97

ITEM	QTY	UNIT PRICE	TOTAL
Control4 C4-HALO-BL Halo Remote	1	$593.97	$593.97

Structured Wiring $300.00

ITEM	QTY	UNIT PRICE	TOTAL
PT **PREWIRE TV** 2 Cat6/1 Shielded Cat6/1 Coax/2 Gang Dual Use Box	1	$300.00	$300.00

Shades $667.86

ITEM	QTY	UNIT PRICE	TOTAL
PD **PREWIRE Data/Power** Cat 6 Shielded and 16/4 for power(Good for all brands)	3	$222.62	$667.86

Main Level > Kitchen $4,750.59

Distributed Audio $1,099.94

ITEM	QTY	UNIT PRICE	TOTAL
PS **PREWIRE Speaker** 1 16/4 Speaker Wire	1	$125.88	$125.88
Episode ES-ESS-BRKT-IC-6 In-Ceiling Speaker Brackets	1	$28.90	$28.90
Triad Speakers TS-PDX-IC64 Triad PDX Series 4 In-Ceiling Speaker (Each) - 6	2	$472.58	$945.16

Lighting $681.98

ITEM	QTY	UNIT PRICE	TOTAL
Control4 C4-KD120-C-SW Contemporary 120V Keypad Dimmer	2	$340.99	$681.98

Network $159.00

ITEM	QTY	UNIT PRICE	TOTAL
Ubiquiti Networks U6-PRO Ceiling-Mounted Wifi 6 Ap With 6 Spatial Streams Designed For Large Offices	1	$159.00	$159.00

Integrated Control System $2,141.81

ITEM	QTY	UNIT PRICE	TOTAL
Apple **IPAD MINI 256GB WIFI [SPACE GRAY] - A17** 7.9 Inch iPad Mini With Wi-Fi - 256Gb - Space Gray	1	$1,319.19	$1,319.19
iPort **CONNECT PRO Case mini A17 BK** IPORT - CONNECT PRO - Case for iPad mini A17 - Black	1	$300.00	$300.00
iPort CONNECT PRO WallStation CONNECT PRO WallStation	1	$300.00	$300.00
PD **PREWIRE Data/Power** Cat 6 Shielded and 16/4 for power(Good for all brands)	1	$222.62	$222.62

Shades $667.86

ITEM	QTY	UNIT PRICE	TOTAL
PD **PREWIRE Data/Power** Cat 6 Shielded and 16/4 for power(Good for all brands)	3	$222.62	$667.86

Main Level > Dining $2,067.80

Distributed Audio $1,099.94

ITEM	QTY	UNIT PRICE	TOTAL
PS **PREWIRE Speaker** 1 16/4 Speaker Wire	1	$125.88	$125.88
Episode ES-ESS-BRKT-IC-6 In-Ceiling Speaker Brackets	1	$28.90	$28.90

	Triad Speakers TS-PDX-IC64 Triad PDX Series 4 In-Ceiling Speaker (Each) - 6	2	$472.58	$945.16

Structured Wiring $300.00

ITEM		QTY	UNIT PRICE	TOTAL
PT	**PREWIRE TV** 2 Cat6/1 Shielded Cat6/1 Coax/2 Gang Dual Use Box	1	$300.00	$300.00

Shades $667.86

ITEM		QTY	UNIT PRICE	TOTAL
PD	**PREWIRE Data/Power** Cat 6 Shielded and 16/4 for power(Good for all brands)	3	$222.62	$667.86

Main Level > Master Bed $6,476.54

Distributed Audio $1,099.94

ITEM		QTY	UNIT PRICE	TOTAL
PS	**PREWIRE Speaker** 1 16/4 Speaker Wire	1	$125.88	$125.88
	Episode ES-ESS-BRKT-IC-6 In-Ceiling Speaker Brackets	1	$28.90	$28.90
	Triad Speakers TS-PDX-IC64 Triad PDX Series 4 In-Ceiling Speaker (Each) - 6	2	$472.58	$945.16

Lighting $1,363.96

ITEM	QTY	UNIT PRICE	TOTAL
Control4 C4-KD120-C-SW Contemporary 120V Keypad Dimmer	4	$340.99	$1,363.96

Network $159.00

ITEM	QTY	UNIT PRICE	TOTAL
Ubiquiti Networks U6-PRO Ceiling-Mounted Wifi 6 Ap With 6 Spatial Streams Designed For Large Offices	1	$159.00	$159.00

Integrated Control System $2,735.78

ITEM	QTY	UNIT PRICE	TOTAL
Apple **IPAD MINI 256GB WIFI [SPACE GRAY] - A17** 7.9 Inch iPad Mini With Wi-Fi - 256Gb - Space Gray	1	$1,319.19	$1,319.19
iPort **CONNECT PRO Case mini A17 BK** IPORT - CONNECT PRO - Case for iPad mini A17 - Black	1	$300.00	$300.00
iPort CONNECT PRO WallStation CONNECT PRO WallStation	1	$300.00	$300.00
PD **PREWIRE Data/Power** Cat 6 Shielded and 16/4 for power(Good for all brands)	1	$222.62	$222.62
Control4 C4-HALO-BL Halo Remote	1	$593.97	$593.97

Structured Wiring $300.00

ITEM		QTY	UNIT PRICE	TOTAL
PT	**PREWIRE TV** 2 Cat6/1 Shielded Cat6/1 Coax/2 Gang Dual Use Box	1	$300.00	$300.00

Shades $667.86

ITEM		QTY	UNIT PRICE	TOTAL
PD	**PREWIRE Data/Power** Cat 6 Shielded and 16/4 for power(Good for all brands)	3	$222.62	$667.86

Security $150.00

ITEM		QTY	UNIT PRICE	TOTAL
PS	**PREWIRE Security - Network** Cat 6-16/4	1	$150.00	$150.00

Main Level > Master Bath $2,203.81

Lighting $1,376.95

ITEM		QTY	UNIT PRICE	TOTAL
	Control4 C4-KD120-C-SW Contemporary 120V Keypad Dimmer	3	$340.99	$1,022.97
	Control4 C4-SW120277-C-SW Contemporary 120/277V Switch	2	$176.99	$353.98

Network $159.00

ITEM	QTY	UNIT PRICE	TOTAL
Ubiquiti Networks U6-PRO Ceiling-Mounted Wifi 6 Ap With 6 Spatial Streams Designed For Large Offices	1	$159.00	$159.00

Shades $667.86

ITEM	QTY	UNIT PRICE	TOTAL
PD **PREWIRE Data/Power** Cat 6 Shielded and 16/4 for power(Good for all brands)	3	$222.62	$667.86

Main Level > Deck $925.88

Distributed Audio $725.88

ITEM	QTY	UNIT PRICE	TOTAL
Episode ES-500-AW-6-BLK Episode All-Weather Series Surface Mount Speakers (Pair)	1	$571.10	$571.10
PS **PREWIRE Speaker** 1 16/4 Speaker Wire	1	$125.88	$125.88
Episode ES-ESS-BRKT-IC-6 In-Ceiling Speaker Brackets	1	$28.90	$28.90

Structured Wiring $200.00

ITEM	QTY	UNIT PRICE	TOTAL
PC **PREWIRE Camera** 1 Cat6/1 Shielded Cat6	1	$200.00	$200.00

Main Level > Hearth $1,680.20

Lighting $340.99

ITEM	QTY	UNIT PRICE	TOTAL
Control4 C4-KD120-C-SW Contemporary 120V Keypad Dimmer	1	$340.99	$340.99

Integrated Control System $593.97

ITEM	QTY	UNIT PRICE	TOTAL
Control4 C4-HALO-BL Halo Remote	1	$593.97	$593.97

Structured Wiring $300.00

ITEM	QTY	UNIT PRICE	TOTAL
PT **PREWIRE TV** 2 Cat6/1 Shielded Cat6/1 Coax/2 Gang Dual Use Box	1	$300.00	$300.00

Shades $445.24

ITEM		QTY	UNIT PRICE	TOTAL
PD	**PREWIRE Data/Power** Cat 6 Shielded and 16/4 for power(Good for all brands)	2	$222.62	$445.24

Main Level > Front Entry $540.99

Lighting $340.99

ITEM		QTY	UNIT PRICE	TOTAL
	Control4 C4-KD120-C-SW Contemporary 120V Keypad Dimmer	1	$340.99	$340.99

Structured Wiring $200.00

ITEM		QTY	UNIT PRICE	TOTAL
PC	**PREWIRE Camera** 1 Cat6/1 Shielded Cat6	1	$200.00	$200.00

Main Level > Office $522.62

Structured Wiring $300.00

ITEM		QTY	UNIT PRICE	TOTAL
PT	**PREWIRE TV** 2 Cat6/1 Shielded Cat6/1 Coax/2 Gang Dual Use Box	1	$300.00	$300.00

Shades $222.62

ITEM	QTY	UNIT PRICE	TOTAL
PD **PREWIRE Data/Power** Cat 6 Shielded and 16/4 for power(Good for all brands)	1	$222.62	$222.62

Main Level > Office 2 $381.62

Network $159.00

ITEM	QTY	UNIT PRICE	TOTAL
Ubiquiti Networks U6-PRO Ceiling-Mounted Wifi 6 Ap With 6 Spatial Streams Designed For Large Offices	1	$159.00	$159.00

Shades $222.62

ITEM	QTY	UNIT PRICE	TOTAL
PD **PREWIRE Data/Power** Cat 6 Shielded and 16/4 for power(Good for all brands)	1	$222.62	$222.62

Main Level > Mudroom Hall $340.99

Lighting $340.99

ITEM	QTY	UNIT PRICE	TOTAL
Control4 C4-KD120-C-SW Contemporary 120V Keypad Dimmer	1	$340.99	$340.99

Main Level > Garage $13,028.31

Lighting $340.99

ITEM	QTY	UNIT PRICE	TOTAL
Control4 C4-KD120-C-SW Contemporary 120V Keypad Dimmer	1	$340.99	$340.99

Network $1,597.00

ITEM	QTY	UNIT PRICE	TOTAL
Ubiquiti Networks UDM-SE Dream Machine Special Edition (UDM SE) Enterprise-Grade UniFi OS Console	1	$499.00	$499.00
Ubiquiti Networks USW-PRO-24 UniFi professional 24 port gigabit swtich with layer 3 features and SFP+	1	$399.00	$399.00
Ubiquiti Networks USW-PRO-24-POE 24-port switch with (16) 802.3at PoE+ ports, (8) 802.3bt PoE++ ports, and (2) 10 GB SFP+ ports	1	$699.00	$699.00

Integrated Control System $7,261.41

ITEM	QTY	UNIT PRICE	TOTAL
Triad Speakers TS-AMS16 AMS Audio Matrix Switch	1	$2,694.29	$2,694.29
Binary B3-STEREOMINIRCA-1 B3 3.5mm Mini Stereo to Dual RCA Male	2	$15.99	$31.98
Binary B5-AUD-1 B5 Analog Audio Cable	6	$33.99	$203.94
Binary B5-AUD-2 B5 Analog Audio Cable	6	$44.99	$269.94

	Binary B5-DIGCOAX-1 B5 Digital Coax Cable	1	$23.99	$23.99
TS	**Triad Speakers TS-PAMP4-125-V2** Triad Power Amplifier	1	$1,765.99	$1,765.99
TS	**Triad Speakers TS-PAMP8-125-V2** Triad Power Amplifier	1	$2,271.28	$2,271.28

Structured Wiring $1,654.99

ITEM		QTY	UNIT PRICE	TOTAL
	Premier Conduit PEC-150T-550 Premier Corrugated, High Density Polyethylene, Reel, Orange, 3/4"	25	$3.00	$75.00
	Strong SR-WMS-18U Wall Mount Rack System	1	$1,579.99	$1,579.99

Control $1,823.93

ITEM		QTY	UNIT PRICE	TOTAL
	Control4 C4-CORE3 Control4 CORE 3 Controller	1	$1,794.94	$1,794.94
	Control4 C4-AK-3M 3M Wireless Antenna Kit	1	$28.99	$28.99

Security $349.99

ITEM	QTY	UNIT PRICE	TOTAL
Cindev CINDEV-QOLSYS Cindev Qolsys Security Driver for Control4. Native integration between Qolsys IQ security panels and Control4. Local communication, SDDP auto-discovery. Supports arming/disarming, zone reporting (up to 8 partitions), user management, zone bypass, and custom zone events. Compatible with OS 3.3+ and X	1	$199.99	$199.99
PS **PREWIRE Security - Network** Cat 6-16/4	1	$150.00	$150.00

Main Level > Garage Exterior $400.00

Structured Wiring $400.00

ITEM	QTY	UNIT PRICE	TOTAL
PC **PREWIRE Camera** 1 Cat6/1 Shielded Cat6	2	$200.00	$400.00

Lower Level > Family Room $2,152.91

Distributed Audio $1,099.94

ITEM	QTY	UNIT PRICE	TOTAL
PS **PREWIRE Speaker** 1 16/4 Speaker Wire	1	$125.88	$125.88
Episode ES-ESS-BRKT-IC-6 In-Ceiling Speaker Brackets	1	$28.90	$28.90

	Triad Speakers TS-PDX-IC64 Triad PDX Series 4 In-Ceiling Speaker (Each) - 6	2	$472.58	$945.16

Network $159.00

ITEM		QTY	UNIT PRICE	TOTAL
	Ubiquiti Networks U6-PRO Ceiling-Mounted Wifi 6 Ap With 6 Spatial Streams Designed For Large Offices	1	$159.00	$159.00

Integrated Control System $593.97

ITEM		QTY	UNIT PRICE	TOTAL
	Control4 C4-HALO-BL Halo Remote	1	$593.97	$593.97

Structured Wiring $300.00

ITEM		QTY	UNIT PRICE	TOTAL
PT	**PREWIRE TV** 2 Cat6/1 Shielded Cat6/1 Coax/2 Gang Dual Use Box	1	$300.00	$300.00

Lower Level > Bar $300.00

Structured Wiring $300.00

ITEM	QTY	UNIT PRICE	TOTAL
PT **PREWIRE TV** 2 Cat6/1 Shielded Cat6/1 Coax/2 Gang Dual Use Box	1	$300.00	$300.00

Lower Level > Bed 2 $1,875.10

Distributed Audio $1,099.94

ITEM	QTY	UNIT PRICE	TOTAL
PS **PREWIRE Speaker** 1 16/4 Speaker Wire	1	$125.88	$125.88
Episode ES-ESS-BRKT-IC-6 In-Ceiling Speaker Brackets	1	$28.90	$28.90
Triad Speakers TS-PDX-IC64 Triad PDX Series 4 In-Ceiling Speaker (Each) - 6	2	$472.58	$945.16

Structured Wiring $300.00

ITEM	QTY	UNIT PRICE	TOTAL
PT **PREWIRE TV** 2 Cat6/1 Shielded Cat6/1 Coax/2 Gang Dual Use Box	1	$300.00	$300.00

Control $475.16

ITEM	QTY	UNIT PRICE	TOTAL
Control4 C4-CA1 CA-1 Hub and Automation Controller	1	$446.17	$446.17
Control4 C4-AK-3M 3M Wireless Antenna Kit	1	$28.99	$28.99

Lower Level > Bed 3 $1,399.94

Distributed Audio $1,099.94

ITEM	QTY	UNIT PRICE	TOTAL
PS **PREWIRE Speaker** 1 16/4 Speaker Wire	1	$125.88	$125.88
Episode ES-ESS-BRKT-IC-6 In-Ceiling Speaker Brackets	1	$28.90	$28.90
Triad Speakers TS-PDX-IC64 Triad PDX Series 4 In-Ceiling Speaker (Each) - 6	2	$472.58	$945.16

Structured Wiring $300.00

ITEM	QTY	UNIT PRICE	TOTAL
PT **PREWIRE TV** 2 Cat6/1 Shielded Cat6/1 Coax/2 Gang Dual Use Box	1	$300.00	$300.00

Lower Level > Bunk Room $1,399.94

Distributed Audio $1,099.94

ITEM	QTY	UNIT PRICE	TOTAL
PS **PREWIRE Speaker** 1 16/4 Speaker Wire	1	$125.88	$125.88
Episode ES-ESS-BRKT-IC-6 In-Ceiling Speaker Brackets	1	$28.90	$28.90
Triad Speakers TS-PDX-IC64 Triad PDX Series 4 In-Ceiling Speaker (Each) - 6	2	$472.58	$945.16

Structured Wiring $300.00

ITEM	QTY	UNIT PRICE	TOTAL
PT **PREWIRE TV** 2 Cat6/1 Shielded Cat6/1 Coax/2 Gang Dual Use Box	1	$300.00	$300.00

Summary

Product + Labor	$55,171.98
Subtotal	**$55,171.98**
Tax	$2,511.11
Total Price	**$57,683.09**

Payment Terms

	Billing Date	Due Date	Amount
Deposit (60%)			$34,609.85
Prewire Materials (10%)			$5,768.31
Prewire Completion (10%)			$5,768.31
Trim/Finish Materials			$0.00
Trim Completion (5%)			$2,884.15
Project Completion and Acceptance (15%)			$8,652.47

Signature

Signature

Date